

Technical Data Sheet

Preinsulation Service

Pre-insulation of PEX pipes with Thermaflex® insulation

Ready to use, flexible PEX water installation for versatile application, insulated with high quality PE foam, with closed cell structure




Benefits

- Easy and quick assembly guaranteed due to low weight and high flexibility of the system
- Save time and labor during assembly
- Failure-free operation of the installation, effective protection against energy losses
- High temperature resistance
- Constant insulation performance strong polyethylene coating to protect proper insulation and durable insulation material

Applications

• Central heating installations, hot and cold water



V1.1 - 30.03.2022



Technical Properties of insulation

EN 14313
EN 14313
-
-
-
EN 14707
EN 13787
EN 13501-1

Availability

- Standard length of the finished product from 25 100 m (depending on the size)
- Type of insulation: ThermaCompact IS, wall thickness 6, 9 mm
- Version: plain or knurled, in blue, red or gray
- Finished product rolled in coil, packed in stretch foil

Working pipe sizes and insulation tolerance				
PEX working tube Ø max. [mm]	Insulation wall thickness [mm]		Longth [m]	
	6 (5.0-7.0)	9 (8.0-10.0)	Length [m]	
16x2,0	16,0-18,0	16,0-18,0	50, 100	
20x2,0	20,0-22,0	20,0-22,0	50, 100	
25x2,5	25,0-27,0	25,0-27,0	25, 50	
26x3,0	26,0-28,0	26,0-28,0	25, 50	
32x3,0	32,0-34,0	32,0-34,0	25, 50	

^{*} minimum order to be agreed