

CITY BREWERY JONGENS VAN DE WIT

A sustainable solution with ThermaSmart PRO





ThermaSmart PRO

Certificates

GOALS

This project was born from the need of the brewery to prevent condensation and minimize the energy loss. The insulation they used before leaked and therefore absorbed moisture. The owner, had been in search of alternatives that could offer a definitive solution to these inconveniences. ThermaSmartPRO was the key solution for this.

PROJECT PROCESS

The project process began with a thorough assessment of the existing insulation and identification of areas with poor insulation and condensation issues. Detailed measurements and analysis were conducted to determine the appropriate quantity of ThermaSmartPro insulation required. The elastomeric insulation successfully replaced with ThermaSmartPRO solution.

RESULTS

The brewery no longer experiences condensation issues, ensuring product quality and system reliability. Additionally, the energy savings attained at least 25%. During an inspection by the environmental agency, they couldn't believe how little energy the brewery consumed. They were only convinced when they saw the photos comparing the old and new situation of the insulation.

"We no longer suffer from condensation issues and have saved a lot of energy since ThermaSmartPro insulation was installed 6 years ago. I would definitely recommend Thermaflex to my fellow brewers."





PROJECT LOCATION

• 's-Hertogenbosch, the Netherlands

AT A GLANCE

Reduced 25% of energy consumption

APPLICATION

Chilled Water

www.thermaflex.com

international@thermaflex.com





